

RENZ LANDSCAPES

LANDSCAPE PROPOSAL

February 27, 2016

Mr. Roger and Dawn Diaz
8705 Forester Lane Apex, NC

\$1,260.00 Planting: The following plants will be removed ...all 10 ligustrums. The following plants will be transplanted and moved to a better location...6 azaleas, 4 yellow spirea, 1 crapemyrtle, 13 lirioppe, 4 Purple Heuchera, 1 3' tall camellia will be planted. Large yellow Holly tree will be raised for better drainage.

1 cubic yard of **topsoil** will be used to installed with plants to help with better drainage.
A total of 3 cubic yards of **Designer Dark Brown mulch** will be spread in beds.

\$ 3,450.00 Patio: Remove stoop. Install Belgard 3 piece Dublin Cobble pavers for area directly under deck. (9.6"x 23') 1)Existing soil will be compacted with a plate tamer to compact soil as much as possible so pavers don't settle. 2) **Install geo-textile fabric** so that sand under pavers does not settle into clay. Screed sand and lay 3 piece pavers in a random pattern. Plastic edging will contain pavers. Polymeric sand will be swept into crack and wetted to firm pavers, prevent weeds, and for looks.

ACTUAL TOTAL PRICE \$4,710.00

Payment is as follows: \$ 1,200.00 .00 upon signing of agreement and \$3,510.00 upon completion.

Thank you for the opportunity to price this work. Please call if you have any questions.

Curt Renz, Renz Landscapes _____

Accepted: _____ Date _____

Tel: 919/460-6364 8638 Macedonia Lake Drive Cary, NC 27518